

C O N T R A C T, of two parts, made this 17th day of July 1899, by and between the HERRESHOFF MANUFACTURING COMPANY, a corporation created under the laws of the State of Rhode Island and doing business at Bristol, in said State, hereinafter called the Party of the First Part, and Mr. G. Oliver Iselin, of New Rochelle New York, hereinafter called the Party of the Second Part, - - - WITNESSETH:--

That for, and in consideration of, the payments to be made as hereinafter provided, the said Party of the First Part hereby agrees to construct in their best manner and of first class materials, one (1) center-board racing yacht having a water line length of 15 feet, and in accordance with the outline specification for one design class as follows:-

- Length over all, - - - - - about 24 feet.
- Water line, - - - - - just under 15 feet.
- Beam on water line, - - - - - 5' 10".
- Draft, without center-board, - - - - - 2' 9".
- Free-board at greatest beam, - - - - - 16".

Frame to be of best quality white oak.
Planking and deck to be single and of cedar 9/16" thick.
Fastening to be of copper and bronze.

Ballast to be of lead, 1000 pounds, placed outside and securely bolted to bottom of keel.

No bowsprit. To be rigged with mainsail, jib, and spinnaker, together with the necessary spars, bronze blocks, standing and running rigging complete for racing.

~~XXXXX~~ No house. To have air tanks sufficient to float boat full of water.

Sail area to be 320 square feet, 256 feet of which shall be in the mainsail. *Usual equipment.*

Boat to be built in the best manner and to be ready for delivery at Bristol, R. I., April 1st, 1899.

In consideration of which the said Party of the Second Part,

(2)


heroby covenants and agrees to and with the said Party of the First Part as follows, that is to say:-

The contract price to be paid, by the said Party of the Second Part, for the said boat delivered at Bristol, R. I., shall be six hundred and eighty (\$680.) Dollars, one third of which ^(\$226.67) shall be payable upon the signing of this contract, the balance, \$353.33, when the boat is ready for delivery as aforesaid.

In witness whereof the respective parties to this contract have set their hands the day and year first above written.

Herreshoff Mfg Co.

Witness as to
John B. Herreshoff
Pres & Treas.
LW Spring


Pres. & Treas